

Cocoa Beach Country Club

Cocoa Beach, Florida

- > **Installation:** TW50
- > **Linear Feet/Meters:** 6700 Linear Feet
- > **Sheet Lengths:** 8-12 foot
- > **Soil Conditions:** Sand
- > **Existing Wall:** Some Areas Rock Armored
- > **General Contractor:** Wharton Smith
- > **Subcontractor/Installer:** Construct Co Inc.
- > **Installation Method:** 1500 Lb JM Vibro Hammer on IH180 Mini Excavator

> **Project Details:**

Cocoa Beach CC is located on a peninsula that is subject to erosion that was threatening the golf course. It was felt that one more major storm event would result in irreparable damage to the course. Tidewall TW50 was installed behind the existing shoreline as a last line of defense against such an event. The sheets were driven below grade, and capped with concrete to provide secure erosion protection that will be completely covered to with soil to protect the aesthetics of this beautiful course.

